

	<b>Houston Retaining Wall</b>				
Item	Description	Unit	Quantity	Estimated	Estimated Total Price
1	Bottom row big block	SF	40	\$94.50	\$3,780.00
2	Special block	SY	0	\$105.00	\$0.00
3	Top row big block	SF	20	\$94.50	\$1,890.00
4	Half block	SF	4	\$78.75	\$315.00
5	Delivery of block	Trips	0	\$525.00	\$0.00
6	Clean Rock	Ton	12	\$18.38	\$220.56
7	Drain Tile	FT	100	\$2.82	\$282.00
8	Base Course	Ton	25	\$0.00	\$0.00
9	Top Soil			\$0.00	
<b>Total Preliminary Probable Construction Cost</b>					<b>\$6,487.56</b>

<b>Grass Options:</b>					
	Grass seed				\$250.00
	Erosion control blanket without seed				\$150.00
	Hydroseeding			\$63.00	\$2,500.00

**NOTES:**

1. Blocks are 2'x4'.
2. Retaining wall will be approximately 70' long and 10-15' wide, 3 block tall with the first block being buried for a footer.
3. Two trees will need to be removed to give space for the wall, the rest will be left.
4. We will install clean rock under the footer blocks and drain tile behind the block wall.
5. We have topsoil that we will spread out and then the options for grass are seeding, erosion control blankets or hydroseeding.